

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5144 EXPIRATION DATE

OPERATOR Mull Drilling Company, Inc. API NO. 15-007-21,563-00-00

ADDRESS P.O. Box 2758 COUNTY Barber

Wichita, KS 67201 FIELD Medicine River

\*\* CONTACT PERSON Patricia Ungleich PROD. FORMATION NA

PHONE 264-6366 or 264-5368

PURCHASER NA LEASE Clarke

ADDRESS WELL NO. #2

WELL LOCATION 150' E of C NE NE

DRILLING D.R. Lauck Oil Company, Inc. 660' Ft. from north Line and

CONTRACTOR ADDRESS 221 S. Broadway, Suite 400 510' Ft. from east Line of

Wichita, KS 67202 the NE (Qtr.) SEC 5 TWP 32S RGE 12W.

PLUGGING Sun Cementing Company WELL PLAT (Office Use Only)

CONTRACTOR ADDRESS P.O. Box 169

Great Bend, KS 67530

TOTAL DEPTH 4198 PBTD NA

SPUD DATE 2/17/83 DATE COMPLETED 2/24/83

ELEV: GR 1482 DF KB 1487

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

			⊕
		5	

KCC ✓  
KGS ✓  
SWD/REP  
PLG.

Amount of surface pipe set and cemented 402.97' DV Tool Used? NA

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Michael R. Kidwell, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Michael R. Kidwell (Signature)  
Michael R. (Name) Kidwell

SUBSCRIBED AND SWORN TO BEFORE ME this 2nd day of March, 1983.

Patricia L. Ungleich (Signature)  
(NOTARY PUBLIC)  
Patricia L. Ungleich

MY COMMISSION EXPIRES: March 27, 1983

RECEIVED STATE CORPORATION COMMISSION

\*\* The person who can be reached by phone regarding any questions concerning this information.

MAR 23 1983

CONSERVATION DIVISION Wichita, Kansas

PATRICIA L. UNGLEICH STATE NOTARY PUBLIC Sedgwick County, Kansas My Appt. Exp. 3/27/83

SIDE TWO

OPERATOR TXO PRODUCTION CORP.

LEASE Clarke

ACO-1 WELL HISTORY (W) SEC. 5 TWP. 32S RGE. 12 (W)

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. "G" #4

Show all important zones of porosity and contents thereof; cored intervals, and all drill-test tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<input checked="" type="checkbox"/> Check if no Drill Stem Tests Run.				
			LOG TOPS	
			Herington	1769 -280
			Towanda	1902 -413
			Cottonwood	2305 -816
			Foraker	2451 -962
			Onaga Sh	2575 -1086
			IC Sand	2584 -1095
			Wabaunsee	2631 -1142
			Topeka	3042 -1553
			Elgin Sd	3387 -1898
			Oread	3441 -1952
			RTD	3500
			LTD	3480
			PBD	3481
			RAN O.H. LOGS	

THE HOLE

RELEASED  
AUG 01 1983  
FROM CONFIDENTIAL

If additional space is needed use Page 2, Side 2

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Seals	Type and percent additives
Surface	12 1/4	8-5/8"	24#	318'		125 100	11% common 2% gel, 3% CaCl
Production		4-1/2"	10.5#	3495'		150	RFC w/additives

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Seals cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A			
TUBING RECORD			4 JSPF	Elgin	3388-96'
Size	Setting depth	Factor set at			
2-3/8"	3437'	3431'			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Dumped 250 gals acetic & 5 bbls formation wtr	

Date of first production 1-7-83	Producing method (flowing, pumping, gas lift, etc.) pumping	Gravity N/A
Estimated Production -I.P. Oil 125 BO Gas None MCF Water N/A % 0 BW Disposition of gas (vented, used on lease or sold) Sold-UPG		Gas-oil ratio N/A CFS
Perforations 3388-96'		

Date: 12-20-82	Customer Order No.	Sec.	Trp.	Range	Track Callout: 2:00pm	On Location: 4:30pm	Job Begins: 7:40pm	Job Completed: 8:00pm
Order: T.X.O.		Contractor: F.W.A #32			Client To: T.X.O.			
Mailing Address		City			State			

Well Name and Party: CLARKE G-4	Price: Med. Lodge 2 1/2 w/tn Barber	County: Barber	State: Kansas
Depth of Well: 355	Depth of Job: 322	Size of Hole Ann. and Kind of Cement: 8 5/8 225#	Cement Left in casing: 20
Kind of Job: Surface Casing		Drilling: <input checked="" type="checkbox"/> X	Truck No.: CT-40

Conditions of Well as seen by Cementer: normal returns

Type of Plug: wooden rubber

Pressure Casing: Minimum Maximum

Time Required Mixing Cement: min. Making Charge: min. Pumping Charge: min.

Price Reference No. 2

Price of Job 379.02

Second Stage

Standby Truck

Other Charges

Pump Truck Mileage 72.00

Ran seven joints of 8 5/8 inch casing to 322 feet cemented with 125# LR-40 3% each followed with 100 sacks of Class A 3% coal 2% gel Displaced plug to 302 feet with FF balls of fresh water cement did circulate

Customer: Mitch

Address: Med. Lodge Kansas

Agent of Contractor or Operator: J. J. [Signature]

Prices Subject to Correction.

**SALES TICKET FOR MATERIALS**

QUANTITY SACKS	BRAND AND TYPE	PRICE	TOTAL
125 SX	LR-40 (Class A)		
100 SX	Class A		
G.C. 890 lbs			
M.V. CL.			
Gel 200 gal			
Plug 1 8 5/8 wooden rubber cap			
Delivered By: T-47		Handling and Drilling: 4	
Delivered From: Med. Lodge		Sales Tax	
Signature of Operator: J. J.		Total Charges	

RELEASED

AUG 0 1983

FROM CONFIDENTIAL