

913

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

DEC 5 1960
12-5-60
CONSERVATION DIVISION
Wichita, Kansas

File No. _____ County: Rush

Location: NW SE NE Sec. 33 Twp. 19 Rge. 16 (E) (W)

Name of Field: _____ Total Depth: 3777

I have this date completed supervision of plugging of:

Lease Name: Williams Nagel Well No. 2

Operator's Full Name: Alkay Oil Co

Complete Address: 612 Kennedy Bldg Tulsa, Oklahoma

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kansas License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 23 Month 11 Year 60

The above well was plugged as follows:

8 5/8" 1092' circulated with cement - 5 1/2" 3768' with 100 sax cement.
Filled with sand to 3760', set 4 sax cement with dump bailer, pulled
2822' 5 1/2" - filled hole with chunk mud to 350', set 20 sax cement at 350',
filled with chunk mud to 125', set 10 sax cement at 125', heavy chunk mud to
35', set bridge and 10 sax cement to bottom cellar,

Signed: Edson Lett
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 12/5/60
INV. NO. 2245-W