

OPB

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 85-40
LOCATION C SE-SE
SEC. 33 TWP. 19 RGE. 16 W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Tammen

Operator Magnolia Petroleum Co. Address Box 770, St. Bend Kans.

Field _____ County Rush

Total Depth 3775 Feet.

Plugging Contractor Ace Pipe Pulling Co.

Plugging Contractor's License No. 2

Address Great Bend Kans.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4" @ 1056' C.W.C. 5 1/2" Oil string
set 3756' w/ 150 sv Cem. Filled back with
Crushed rock to 3745' and dumped 5 sv Cem.
Shot off and pulled 5 1/2" casing. mudded hole
to 300' set rock bridge and run 20 sv Cem.
mud to 35' rock bridge and 10 sv Cem. to
base of cellar

Warren H. Horner
District Conservation Agent

Date Dec. 28, 1954

PLUGGING
FILE SEC 33 T 19 R 16W
BOOK PAGE 85 LINE 40

RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1954
12-30-54
CONSERVATION DIVISION
WICHITA, KANSAS