

R

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1959
12-30-59
CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rush

Location: SW SE SW Sec. 33 Twp. 19 Rge. 16 (E) (W)

Name of Field: _____ Total Depth: 3770

I have this date completed supervision of plugging of:

Lease Name: Tammen Well No. 1

Operator's Full Name: Ben F. Brack Oil Co Inc

Complete Address: 310 Brown Bldg Wichita, Kans

Plugging Contractor: Clay Pipe Pulling Co

Address: Ellinwood, Kans License No. _____

Oil Well Gas Well Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 12 Month 26 Year 59

The above well was plugged as follows:

8 5/8" 1064' circulated with 500 sax cement - 5 1/2" 3740' with 100 sax cement behind.

Filled with sand to 3700', set 4 sax cement with dump bailer, recovered 2000' 5 1/2" - run tubing in hole to approx 700', circulated hole with heavy mud through 2" tubing (Gel Mud), displaced 20 sax cement through 2" tubing at 420', heavy mud to 45', circulated hole full cement from 45' to 0' through 2" tubing.

Mudding and cementing by Halliburton Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 1/14/60
INV. NO. 688-w