

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R
CPB

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 135-32 County: Barber

Location: NE NW SE Sec. 20 Twp. 30 Rge. 15 (E) (W) X

Name of Field: _____ Total Depth: 4637

I have this date completed supervision of plugging of:

Lease Name: Gypsum "A" Well No. 2

Operator's Full Name: Aladdin Petroleum Corp.

Complete Address: 809 Petroleum Bldg., Wichita, Kans.

Plugging Contractor: R & S Pipe Pulling Co.

Address: Hoisington, Kans. License No. 1

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 9 AM Day 4 Month November Year 1958

The above well was plugged as follows:

844' of 10 $\frac{3}{4}$ " surface casing circulated with 300 sack cement. 7" set at
4502. Top Perf 4414. Hole was sanded to 4410' and 5 sack cement dumped
with dump bailer. Hole was filled to 265 with heavy mud with rock bridge
set from 265'. 30 sack cement placed top rock bridge. Heavy mud to 35'.
A rock bridge was set from 35' with 15 sack cement to base of cellar.

Signed: *[Signature]*
Conservation Division Agent

Reviewed: *[Signature]*
Field Supervisor

Remarks:

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 20 T. 30 R. 15W
BOOK PAGE 135 LINE 32