

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

NOV 1 1965

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Ferguson Oil Company

Complete Address: 1505 Wichita Plaza, Wichita, Kansas

Lease Name Lee "A" Well No. # 1

Location C NW SW Sec. 4 Twp. 30 Rge. 15 (E)    (W) W

County Barber Total Depth 4915'

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X

Other well as hereafter indicated:   

Plugging Contractor: Walters Drilling Company

Address: 510 Orpheum Bldg., Wichita, Kansas License No.   

Operation Completed: Hour 1:00 PM Day 29th Month Oct. Year 1965

The Above well was plugged as follows:

247' of 8 5/8" surface pipe, cement circulated with 180 sacks. Hole  
was filled with drilling mud to 240', 1st cementing plug, bridged solid  
with dry cement and hulls on fluid at 240', and cemented with 25 sacks.  
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged  
solid with dry cement and hulls on fluid at 40', and cemented with 10  
sacks to the base of the cellar. Rat hole bridged and cemented with 2  
sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

**INVOICED**

DATE 11/1/65  
INV. NO. 2061-41