

10 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 29 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management Inc.

Complete Address: Box 922, Great Bend, Kansas

Lease Name Moffett Well No. # 1

Location SE SE SW Sec. 16 Twp. 30 Rge. 15 (E) (W) X

County Barber Total Depth 4610

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 2:00PM Day 27th Month Jan. Year 1964

The Above well was plugged as follows:

321' of 8 5/8" surface pipe, cement circulated. 4610' of 4 1/2" long string,
cemented with 175 sacks. Plug back to 4246'. Top perforation 4233'. Bottom
of hole was sanded to 4200', and cemented with 3 sacks. Fluid in hole was
at 290', plug was set at 290', with 10' rock bridge, and cemented with 25
sacks. Hole was filled with mud to 40', with 10' rock bridge, and cemented
with 10 sacks to base cellar.

3950' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 1/29/64

INV. NO. 8552-W