

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued March 27, 1967.

Operator's Full Name Magic Circle Oil Company

Complete Address: Box 16557, Oklahoma City, Oklahoma

Lease Name National Gypsum Well No. # 1

Location C NE NE Sec. 19 Twp. 30 Rge. 15 (E) (W) W

County Barber Total Depth 4685'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No.     

Operation Completed: Hour 10:30AM Day 1st Month April Year 1967

The Above well was plugged as follows:

249' of 8 5/8" surface pipe, cement circulated. 4640' of 4 1/2" long string,  
cemented with 130 sacks. Plug back T.D. 4610'. Top perferation 4490'.  
Bottom of the hole was sanded to 4475', and cemented with 3 sacks, through  
the dump bailer. 3860' of 4 1/2" long string was recovered from the hole.  
Fluid level in the hole was at 250', bridge plug and rock bridge from  
250' to 240', and cemented with 25 sacks. Hole was filled with mud to  
40', rock bridge from 40' to 30', and cemented with 10 sacks to the base  
of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Audie Elving  
Well Plugging Supervisor

DATE 4/3/67  
INV. NO. 4991-W