

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 95-42.
990' F. W. 405' N. E. 75' S. of Location
LOCATION NE-NW-NW
SEC. 9 TWP. 30 RGE. 15W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Moffett
Operator Sinclair Oil-Gasco Address 21537 Chase Paris
Field _____ County Barber
Total Depth 4876 Feet.

(Describe briefly the manner in which the well was plugged)

13" 145' Circulated with Cement 200 st
5 1/2" 4875' cemented with 150 st. cement
drilled out to 4808. Job Perforation 4635-4656
filled with gravel to 4635' cement to 4583'
Pulled 3976' 5 1/2" filled with Mud to 275' set rock
bridge run 25' st cement filled with mud and
rock to 145' chat to 140' cement to 118' Mud to
40' heavy rock bridge to 20' cement to face of
cellar.

Pipe Pulling 9m

Pulling conts.

Alfred Dutgers, Jr.

RECEIVED
STATE DEPT. OF COMMISSION

MAY 16 1953

M. L. Riess
District Conservation Agent

Date 5-13-53

PLUGGING

FILE SEC 9 T 30 R 15W
BOOK PAGE 95 LINE 42

CONSERVATION DIVISION
Wichita, Kansas