

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 28, 1967.

Operator's Full Name Mull Drilling Company, Inc.

Complete Address 1625 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name Wheelock Well No. # 1

Location C SW NW Sec. 3 Twp. 32 Rge. 12 (E) (W)W

County Barber Total Depth 4449'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling, Inc.

Address Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 4:00 P.M. Day 10th Month August Year 1967

The above well was plugged as follows:

239' of 8 5/8" surface pipe, cemented with 200 sacks. 4297' of 4 1/2" long string, cemented with 125 sacks. Plug back T. D. 4248'. Top perforation 4227'. Bottom of the hole was sanded to 4200', and cemented with 5 sacks, through the dump bailer, with cement from 4200' to 4160'. 2200' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 230', bridge plug and rock bridge from 230' to 220'. 6 sacks of cement was mixed in a barrel, and put on plug at 220', through the dump bailer. Next day hole was bailed dry and 19 sacks of cement was added to the plug, with cement from 220' to 145'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 8/14/67

INV. NO. 6119-W