

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

*E*  
*CB*

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 135-33 County: Barber

Location: ~~NE NE SE~~ SW NW SE Sec. 17 20 Twp. 30 Rge. 11 18E (W) X

Name of Field: \_\_\_\_\_ Total Depth: 4451

I have this date completed supervision of plugging of:

Lease Name: National Gypson ". " Well No. 1

Operator's Full Name: Aladdin Petroleum Corp

Complete Address: 809 Petroleum Bldg., Wichita, Kans.

Plugging Contractor: Glenn & Smith Casing Pulling Co.

Address: Ellenwood, Kans. License No. \_\_\_\_\_

Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No X

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 1PM Day 13 Month November Year 1958

The above well was plugged as follows:

165' og 13 3/8" surface casing circulated with cement. Top Perf 4345'.  
Hole was filled with sand to 4340' and 5 sack cement dumped with dump  
bailer. Pipe shot and pulled. Hole filled to 165' with heavy mud. A rock  
bridge set from 165 to 155' with 30 sack cement dumped top plug. Heavy mud  
to 30' with a 10' rock bridge set and 15 sack cement to base of cellar.

Signed: *[Signature]*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

STATE CORPORATION COMMISSION  
NOV 19 1958  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 20 T. 30 R. 15W  
BOOK PAGE 135 LINE 31