

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

OCT 14 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Appleton Oil Company

Complete Address: 506 Beacon Bldg., Tulsa, Oklahoma

Lease Name Schupbach Well No. # 2

Location NE NE NE Sec. 10 Twp. 34 Rge. 11 (E) (W) W

County Barber Total Depth 4660'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 3:30PM Day 8th Month Oct Year 1966

The Above well was plugged as follows:

358' of 8 5/8" surface pipe, cement circulated, 4658' of 4 1/2" long string,
cemented with 100 sacks. Plug back T.D. 4630'. Top perferation 4524'.
Bottom of the hole was sanded to 4500', and cemented with 3 sacks.
4100' of 4 1/2" long string was recovered from the hole. Fluid level in
the hole was at 300', bridge plug and rock bridge from 300' to 290',
and cemented with 25 sacks. Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/14/66
INV. NO. 4098-U

Signed: Archie Elving
Well Plugging Supervisor