

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued April 26, 1967.

Operator's Full Name Leben Drilling, Inc.

Complete Address: P. O. Box 486, Great Bend, Kansas 67530

Lease Name Groendyke Well No. # 1

Location NW NW NW Sec. 8 Twp. 34 Rge. 11 (E) (W) W

County Barber Total Depth 4620'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 2:45PM Day 2nd Month May Year 1967

The Above well was plugged as follows:

290' of 8 5/8" surface pipe, cemented with 275 sacks, 4620' of 4 1/2" long
string, cemented with 100 sacks. Plug back T.D. 4598'. Top perforation
4580'. Bottom of the hole was sanded to 4550', and cemented with 5 sacks,
through the dump bailer. 3800' of 4 1/2" long string was recovered from the
hole. Fluid in the hole was bailed down to 280', bridge plug and rock
bridge from 280' to 270', and cemented with 25 sacks. Hole was filled
with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks
to the base of the cellar.

I hereby certify that the above well was plugged as stated.

INVOICED

DATE 5/5/67
INV. NO. 5166-U

MAY 5 1967

Signed: Audie Elving
Well Plugging Supervisor

CONSERVATION DIVISION
Wichita, Kansas