

KANSAS

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 19 1966

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Roy D. McAninch  
 Complete Address: 1363 First National Bldg., Oklahoma City, Oklahoma  
 Lease Name Dorothy Well No. # 1  
 Location C SW NE Sec. 26 Twp. 34 Rge. 11 (E) (W) W  
 County Barber Total Depth 4690'  
 Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
 Other well as hereafter indicated:       
 Plugging Contractor: Hellar Drilling Company, Inc.  
 Address: 1014 Union Center, Wichita, Kansas License No.       
 Operation Completed: Hour 1:00PM Day 14th Month July Year 1966

## The Above well was plugged as follows:

301' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole  
was filled with drilling mud to 275, 1st cementing plug, bridged with  
1/2 sack of hulls on fluid at 275', and cemented with 25 sacks. Hole  
was filled with drilling mud to 40', 2nd cementing plug, bridged with  
1/2 sack of hulls on fluid at 40', and cemented with 10 sacks to the  
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlise Elving  
Well Plugging SupervisorDATE 7/19/66  
INV. NO. 3584-W