

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued February 3, 1967.

Operator's Full Name Dorset Company

Complete Address: 610 National Bank of Tulsa Bldg., Tulsa, Oklahoma.

Lease Name Baker Well No. # 1

Location SW SE Sec. 8 Twp. 32 Rge. 8 (E) (W) W

County Harper Total Depth 4410'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Winfield Oil Field Service, Inc.

Address: Box 952, Winfield, Kansas License No. 531

Operation Completed: Hour 11:30AM Day 6th Month Feb. Year 1967

The Above well was plugged as follows:

231' of 8 5/8" surface pipe, cemented with 200 sacks. 4404' of 5 1/2" long
string, cemented with 50 sacks. This is an open hole. Bottom of the hole
was sanded to 4390', and cemented with 5 sacks, through the dump bailer.
3650' of 5 1/2" long string was recovered from the hole. Fluid level in the
hole was at 240', bridge plug and rock bridge from 240' to 230', and cement-
ed with 25 sacks. Hole was filled with mud to 40', rock bridge from 40'
to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/10/67
INV. NO. 4738-W