

KANSAS

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 7 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Well Plugging Authority,  
issued February 26, 1968.

Operator's Full Name Dorset Company  
 Complete Address: 610 National Bank of Tulsa Bldg., Tulsa, Oklahoma 74103  
 Lease Name Robinson Well No. # 1  
 Location C NE NE Sec. 17 Twp. 32 Rge. 8 (E) (W) W  
 County Harper Total Depth 4362'  
 Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
 Other well as hereafter indicated: \_\_\_\_\_  
 Plugging Contractor: Flint Engineering & Construction Company  
 Address: Box 950, Eldorado, Kansas 67042 License No. 547  
 Operation Completed: Hour 1:00PM Day 4th Month March Year 1968

The Above well was plugged as follows:

235' of 8 5/8" surface pipe, cemented with 200 sacks. 4361' of 5 1/2" long string, cemented with 50 sacks. This is an open hole. Bottom of the hole was sanded to 4300', and cemented with 5 sacks, through the dump bailer, with cement from 4300' to 4260'. 4062' of 5 1/2" long string was recovered from the hole. Hole was filled with mud to 240', rock bridge from 240' to 230', and cemented with 25 sacks, with cement from 230' to 155'. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

3/7/68

INV. NO.

7381-W

Signed:

Audie Elving  
Well Plugging Supervisor