

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 077 - 20596 - 00 - 00 (of this well)

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 200 W. Douglas, Suite 300, Wichita, Ks. 67202

Lease Name Robinson "E" Well No. 1

Location SW SE Sec. 17 Twp. 32s Rge. 8 (E) (W) X

County Harper Total Depth 3960

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Clarke Corp.

Address 107 W. Fowler, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 11:30 Am. Day 29 Month 9 Year 1980

The above well was plugged as follows:

202' 8 5/8" casing w/200 sax cement. 2 7/8" casing set at 3959' w/400
sax cement. CIBP set at 3700' & at 3090' - Top pref's at 3062 to 3066'
Howco mixed & pumped 20 sax common cement in 2 7/8" casing to 2462'.
Pull 2000' casing - Howco mixed & pumped in 8 5/8" casing 8 sax hulls
25 sax gel, 125 sax 50/50 posmix cement w/3% cc to top of casing.
Shut in w/400# pressure.

RECEIVED
STATE CORPORATION COMMISSION

OCT - 2 1980

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE

10-10-80

INV. NO.

3063307W