

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Nov 18, 1967.

RECEIVED
STATE CORPORATION COMMISSION
NOV 20 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Carlson & Faulconer

Complete Address: 336 Union Center Wichita, Kansas.

Lease Name Brooks Well No. #1

Location NW-NW-SE Sec. 32 Twp. 31 Rge. 13W (E) (W) W

County Barber Total Depth 4840'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply

Address: Box 562 Great Bend, Kansas. License No. 490

Operation Completed: Hour 6:PM Day 17 Month Nov. Year 1967.

The Above well was plugged as follows:

210 ft. of 13 3/8" surface pipe circulated with cement. 4449 ft. of 5 1/2"
pipe. Top perforation at 3739'. Plug set at 3700' & 5 sacks cement.
Mud to 210', 10' rock bridge & 35 sacks cement. Mud to 40', 10' rock
bridge & 15 sacks cement, to base of cellar. 3000' of 5 1/2" pipe pulled.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/21/67
INV. NO. 6921-U

Signed: Herman Justus
Well Plugging Supervisor