

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 5 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Rock Island Oil & Refining Company

Complete Address: 321 West Douglas, Wichita, Kansas

Lease Name Smith Well No. # 1

Location C SW NE Sec. 21 Twp. 31 Rge. 13 (E) (W) W

County Barber Total Depth 4669

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling Inc.

Address: 905 Central Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 3:30PM Day 3rd Month May Year 1964

The Above well was plugged as follows:

293' of 8 5/8" surface pipe, cemented with 225 sacks. Hole was filled
with drilling mud to 250', 1st cementing plug, bridged with hulls, and
cemented with 25 sacks, through the drill pipe. Hole was filled with
drilling mud to 40', 2nd cementing plug, bridged with hulls, and cement-
ed with 10 sacks to base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 5/5/64

INV. NO. 9092-W

Signed: Archie Elving
Well Plugging Supervisor