

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 3 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Champlin Oil & Refining Co.

Complete Address: P. O. Box 308, Ellinwood, Kansas

Lease Name Susie H. Smith Well No. # 1

Location NE NE NW Sec. 24 Twp. 31 Rge. 13 (E) (W) W

County Barber Total Depth 3650

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 10:00AM Day 1st Month Feb. Year 1964

The Above well was plugged as follows:

190' of 10 3/4" surface pipe, cemented with 160 sacks. 3649' of 7"  
long string, cemented with 125 sacks. Top perforation 3576'. Bottom  
of hole sanded to 3560', and cemented with 5 sacks. Hole was bailed  
down to 250', Plug set at 250', bridged with 10' of rock, and cemented  
with 40 sacks, bringing the cement to 180' in the surface pipe. Hole  
was filled with mud to 40', 10' rock bridge, and cemented with 15 sacks  
to base cellar.

2895' of 7" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

INVOICED

DATE 2/6/64

INV. NO. 8599-W