

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 - 1968
CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Administrator
500 Insurance Building
Wichita 2, KansasIntent to Drill,
filed February 27, 1968.Operator's Full Name TilcoComplete Address: 815 Wichita Plaza Bldg., Wichita, Kansas 67202Lease Name Smith Well No. # 1Location C NE SW Sec. 27 Twp. 31 Rge. 13 (E) (W) WCounty Barber Total Depth 3778'Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling, Inc.Address: 815 Wichita Plaza Bldg., Wichita, Ks. 67202 License No. _____Operation Completed: Hour 4:00PM Day 5th Month March Year 1968

The Above well was plugged as follows:

320' of 8 5/8" surface pipe, cement circulated with 275 sacks. Hole was filled with drilling mud to 275', 1st cementing plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 275', and cemented with 24 sacks, with cement from 265' to 190'. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and cemented with 9 sacks, with cement from 30' to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/7/68INV. NO. 7376-WSigned: Aushie Elving
Well Plugging Supervisor