


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
311 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barber County, Sec. 34 Twp. 32 Rge. (E) 12 (W)
Location as "NE/CNW%SW%" or footage from lines 100' N of NE NE
Lease Owner Lario Oil & Gas Company
Lease Name Randels Well No. 2
Office Address 301 S. Market St., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 20 19 67
Application for plugging filed May 31 19 67
Application for plugging approved May 23 19 67
Plugging commenced May 20 19 67
Plugging completed May 20 19 67
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4808 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	257	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from total depth to 250'. 2 sacks dry cement, 1 sack hulls, and 25 sacks cement to 155'. Mud from 155' to 40'. 10 sacks cement to base of cellar. 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. R. Kelsey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *G. R. Kelsey*
301 S. Market, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of May, 19 67

My commission expires

July 21, 1970

Frances Leshe

Notary Public.

LARIO OIL & GAS COMPANY
 Randels No. 2
 100' North of NE NE Sec. 34-32S-12W
 Barber County, Kansas

Drilling Commenced: May 7, 1967
 Drilling Completed: May 20, 1967
 Drilling Contractor: Gabbert-Jones, Inc.
 Total Depth 4808'
 I.P. - Dry & Abandoned

Casing Record
 8 5/8" 257' Cem. w/ 225 sacks

<u>Formation</u>	<u>Depth</u>	<u>Elec. Log Tops</u>	
Red rock & clay	100	Elgin Zone	3418' (-1900)
Red rock & shale	815	Elgin Sand Zone	3466' (-1948)
Anhydrite	840	Heebner	3599' (-2081)
Shale	1450	Snyderville Sand	3620' (-2102)
Shale & lime	3635	Douglas Sand Zone	3687' (-2169)
Sand & shale	3795	Brown Lime	3791' (-2273)
Lime	4514	Lansing	3796' (-2278)
Lime & shale	4655	Base Kansas City	4240' (-2722)
Lime & dolomite	4676	Mississippian	4366' (-2848)
Lime & chert	4713	Kinderhook	4544' (-3026)
Lime	4735	Chattanooga	4614' (-3096)
Simpson (cored)	4808	Viola	4649' (-3131)
		Simpson Shale	4743' (-3225)
		Good Simpson Sand	4761' (-3243)
		Base Good Simpson Sand	4767' (-3249)
		Elec. Log T.D.	4807

RECEIVED
 STATE CORPORATION COMMISSION

JUN 1 1967

CONSERVATION DIVISION
 Wichita, Kansas