

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Barber County, Sec. 34 Twp 32S Rge. 12W (E) (W)

Location as "NE/CNWxSWx" or footage from lines NE SW SE
Lease Owner Texaco Inc.
Lease Name E. Meadows Well No. 1
Office Address P. O. Box 2420 - Tulsa, Okla. 74102
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 6/9/67 19
Application for plugging filed Yes 19
Application for plugging approved 19
Plugging commenced 10/8/71 19
Plugging completed 10/8/71 19
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 3/6/71 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation Simpson Depth to top _____ Bottom 4831 Total Depth of Well 4831 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Simpson	Oil	4822	4831	4-1/2"	--	3764'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows:

4831-4806' sd, 4806-4776 cmt, 4776-250 well fluid & mud,
250-240' rock bridge, 240-4' cmt.

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Clark Oil Field Service Inc.
Address Medicine Lodge, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Dewey H. Jordan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dewey H. Jordan
P. O. Box 2420 - Tulsa, Oklahoma 74102
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October, 19 71

My commission expires 11/25/74

W. M. Tolle
W. M. Tolle Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 8 1972
 CONSERVATION DIVISION
 Wichita, Kansas

ELIZABETH MEADOWS #1
 NE SW SE SECTION 34-32S-12W
 BARBER COUNTY, KANSAS

COMMENCED: MAY 10, 1967
 COMPLETED: MAY 25, 1967

OPERATOR - TEXACO INC.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	85	RED ROCK	
85	265	RED BED, SHALE AND SHELLS	RAN 7 JOINTS 8-5/8" CASING, SET @ 265' w/200 SACKS CEMENT.
265	1009	RED BED, SHALE AND SHELLS	
1009	1695	SHALE AND SHELLS	
1695	2090	SHALE AND LIME	
2090	2475	LIME	
2475	3710	LIME AND SHALE	
3710	4568	LIME	
4568	4713	LIME AND SHALE	
4713	4806	LIME	
4806	4831	SAND	
4831	TD		RAN 150 JOINTS 4 1/2" CASING, SET @ 4822' w/75 SACKS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE NE SW SE SECTION 34-32S-12W, BARBER COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 31ST DAY OF MAY, 1967, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton

 BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.