


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County, Sec. 31 Twp. 32S Rge. 12 XXX (W)

Location as "NE/CNW/SW" or footage from lines C NW SW
Lease Owner Bowers Drilling Company, Inc.
Lease Name Noble Well No. 1
Office Address 416 Union Center Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 22 19 63
Application for plugging filed July 24 19 63
Application for plugging approved Yes, verbally July 22 19 63
Plugging commenced July 22 19 63
Plugging completed July 22 19 63
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4625 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: SIZE 8-5/8", PUT IN 281'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 275'
Set first plug at 275' w/25 sax cement, 1/4 sax hulls
Filled with heavy mud to 40'
Set second plug at 40' with 15 sax cement, 1/4 sax hulls

RECEIVED STATE CORPORATION COMMISSION

JUL 29 1963

CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bowers Drilling Company, Inc.
Address 416 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] 416 Union Center, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of July, 19 63

[Signature]

My commission expires May 1, 1966

Notary Public.

WELL LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1963

Bowers Drilling Company, Inc.
Bowers Drilling Company, Inc.
Noble #1
C NW SW Section 31-32S-12W
Barber County, Kansas

COMMENCED:
COMPLETED:
ELEVATION:

CONSERVATION DIVISION
Wichita, Kansas

7-9-63
7-22-63
1690 K.B.

0 - 281	Shale	
281 - 460	Redbed	
460 - 1580	Redbed and shale	
1580 - 1830	Shale - lime streaks	
1830 - 4100	Lime and shale	
4100 - 4137	K.C. lime	Ran 7 jts 8-5/8" casing set at 281'
4137 - 4625	Lime and shale	with 175 sacks
4625	Total Depth	

LOG TOPS:

Heebner	3804	Mississippi Chert	4519
Douglas Sand	3881	Mississippi Limestone	4530
Lansing	3982	Log T. D.	4625
Base K.C.	4362		

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Noble #1, C NW SW Section 31-32S-12W, Barber County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Emil E. Bowers
Emil E. Bowers

Subscribed and sworn to before me, a Notary Public in and for Sedgwick County, Kansas, this 24th day of July, 1963.

Donna F. Miller
Donna F. Miller, Notary Public

My commission expires May 1, 1966