

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barber County, Sec. 31 Twp. 32S Rge. 12 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C SE SE SW

Lease Owner Orville H. Parker

Lease Name Alexander Well No. 3

Office Address 402 A.C. Office Bldg., Arkansas City, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-8 19 52

Application for plugging filed 7-16 19 53

Application for plugging approved 7-17 19 53

Plugging commenced 7-20 19 53

Plugging completed 7-25 19 53

Reason for abandonment of well or producing formation Non-commercial

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Douglas Sd Depth to top 3913 Bottom 3934 Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Elgin Sd	WTR	3706	3728			
Douglas Sd	WTR & GAS	3913	3934			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled up bottom of hole to 3910 with Pea Gravel and ran 5 sacks of cement up to 3830
Filled hole with mud
Pulled 1425.15 feet of 4 1/2 casing
Set bridge @ 300 ft and ran 35 sacks cement
Filled hole with mud to 35 feet from top of hole
Ran 10 sacks cement in top

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1953
CONSERVATION DIVISION
Wichita, Kansas
8-19-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Smith & Elliston

Address P.O. Box 265, Ada, Oklahoma

STATE OF Kansas COUNTY OF Cowley, ss.

Robert L. Jones (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert L. Jones
Arkansas City, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of August, 1953
Carl B. Remer Notary Public.

My commission expires August 1, 1956

PLUGGING
FILE SEC 31 T 32 R 12W
BOOK PAGE 115 LINE 35

ORVILLE H. PARKER
ALEXANDER No. 3
SE SE SW Sec. 31-32S-12W,
Barber County, Kansas


Drilling Started 9-23-52
Drilling Finished 10-8-52

FORMATION

Surface	0 - 217
Red Bed & Shell	217 - 650
Red Bed Shale & Shells	650- 1135
Red Bed Shale & Shells	1135 - 1350
Shale & Shells	1350 - 1455
Shale & Shells	1455 - 1525
Lime & Shale	1525 - 1670
Shale	1670 - 1715
Lime	1715 - 1820
Lime	1820 - 1840
Shale & Lime	1840- 1900
Lime	1900 - 2010
Shale & Lime	2010 - 2345
Lime	2345 - 2430
Lime & Shale	2430 - 2520
Lime	2520 - 2570
Lime & Shale	2570 - 2620
Lime	2620 - 2675
Sandy Lime	2675 - 2700
Lime, Shale	2700 - 2990
Sandy Shale & Lime	2990 - 3035
Lime & Shale	3035 - 3120
Lime	3120 - 3178
Shale, Lime	3178 - 3215
Lime	3215 - 3503
Lime & Shale	3503- 3727
Sand & Shale	3727 - 3800
Lime & Shale	3800 - 3913
Sand Douglas	3913 - 3923
Total Depth	3923

Set 3915' $4\frac{1}{2}$ " 11# Casing cem/ 100 sx.

Drilled deeper to 3934 cable tool datum.



RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1953

6-21-53

CONSERVATION DIVISION
Wichita, Kansas