

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-073-01729-0000
 Spot: SWSWNWSE Sec 8 Twp 28 S Rng 10 ☒ E / ☐ W
1401 Feet from ☐ N / ☒ S Line of Section
2615 Feet from ☒ E / ☐ W Line of Section
 GPS: Lat: 37.625000 Long: 96.335380 Date: 2/12/13
 Lease Name: Alan Seimears (Piedmont) Well #: PIE 01
 County: Greenwood Total Vertical Depth: 435 feet

Operator License No: 101 String Size Depth Pulled Comments
 Op Name: State of Kansas SURF - Casing 12.000 8
 Address 1: 130 S. MARKET
 Address 2:
 City: WICHITA
 State: KS Zip Code: 67202

Well Type: COR - Core Hole (oil) UIC Docket No.: Date/Time to Plug: 4/4/13 /
 Plug Co License No.: 3097 Plug Co. Name: K-W OIL WELL SERVICES, INC.
 Proposal Rcvd from: Robert Kepley Company Name: K-W Phone: (620) 431-2285

Fill well with portland cement from TD to surface.

Proposed
Plugging
Report:

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 4/4/13 / KCC Agent: FRANK GUILFOYLE

Actual Plugging Report: Perfs: Top Bottom Thru
 Dig out location where water seeping out of ground. Find bore hole and set some surface pipe. Had Westar Energy move overhead electric lines away from location for safety reasons. Set up drill rig and start reaming bore hole. Drill and ream hole to the depth of 435 ft and started drilling new hole. Gelled hole, then pump portland cement fro 435 ft to surface. Pull drill steel and top off well. Pump total of 112 sacks of cement. Well plugged.

Remarks: Contract No. 11782. Control No. 20130069-001. Reg. Sec. GPS'ed by Mike Heffern
NAD83

Plugged Thru: DP - Drill Pipe RECEIVED KANSAS CORPORATION COMMISSION Plugged Due to Compliance Issue: ☐ Yes ☒ No
 District: 03 JUN 04 2013 CONSERVATION DIVISION WICHITA, KS
 (Technician)
 Form: District Plugging Report -