

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07267-00-00
Spot: NESENE Sec/Twnshp/Rge: 36-18S-11W
3563 feet from S Section Line, 297 feet from E Section Line
Lease Name: MUSENBERG Well #: 2
County: BARTON Total Vertical Depth: 3333 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3200		
SURF	8.625	138		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/23/2013 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: KCC Phone: (620) 727-3409

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/600 # hulls and 11 sx gel.
Perforations: 200', 500' and 1350'
Control # 201 30071-2002

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/23/2013 7:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Worked tubing down to 3100' and pumped 11 sx gel followed by 50 sx cement w/200 # hulls.
Pulled tubing to 1350' and pumped 75 sx cement w/300 # hulls. Pulled tubing to 500' and
pumped 75 sx cement. POOH. Hooked to casing and pumped 175 sx cement. Cement
circulated out braden head and into pit.

GPS: 38.44446 -098.48166

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 03 2013


CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICES TICKET # 5972 FEE FUND PROJECT MUSENBERG "MARY IDA UNIT"
CONTROL # 201 30071-2002

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

SEP 30 2013