

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-091-20159? - 0000

Spot: NWNESWSW Sec 16 Twp 15 S Rng 23 ☒ E / ☐ W

1108 Feet from ☐ N / ☒ S Line of Section

4520 Feet from ☒ E / ☐ W Line of Section

GPS: Lat: 38.741351 Long: 94.868937 Date: 11/16/12

Lease Name: Ramey A (Potra+2) Well #: RAM 01

County: Johnson Total Vertical Depth: 625 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>SURF - Casing</u>	<u>6.250</u>	<u>20</u>	<u>0</u>	<u>EST</u>
Address 1: <u>130 S. MARKET</u>	<u>PROD - Casing</u>	<u>2.000</u>	<u>625</u>	<u>0</u>	<u>EST</u>
Address 2: _____	_____	_____	_____	_____	_____
City: <u>WICHITA</u>	_____	_____	_____	_____	_____
State: <u>KS</u> Zip Code: <u>67202</u> - _____	_____	_____	_____	_____	_____

Well Type: GAS - Natural Gas - Production UIC Docket No.: _____ Date/Time to Plug: 6/12/13 / _____

Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.

Proposal Rcvd from: MIKE KEPLEY Company Name: KWS Phone: (620) 431-8945

Proposed
Plugging
Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt. II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%

Date/Time Plugging Completed: 6/12/13 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Run 1" to 300 ft with reamer. Pull 1" out to perforate. Perforate at 300, 150 and 75 ft. Run 1" to 625 ft. Wash and hit hard at 625 ft. Pump Portland cement from TD to surface. Pull pipe and top off well. Pump total of 28 sacks of cement. Well plugged.	75	300	CSG - Casing	

Remarks: Contract # 11782. Control # 20130076-001. Irregular Sec. GPS by Taylor Herman
NAD83

Plugged Thru: TBG - Tubing RECEIVED KANSAS CORPORATION COMMISSION Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03 AUG 02 2013 CONSERVATION DIVISION WICHITA, KS Frank Guilfoyle (Technician) Form: District Plugging Report - _____