

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-20968-00-00
Spot: SWNW Sec/Twnshp/Rge: 18-35S-2E
feet from Section Line, feet from Section Line
Lease Name: NORRIS TULSOIL AND GAS Well #: 1-18
County: SUMNER Total Vertical Depth: 925 feet

Operator License No.: 100
Op Name: KANSAS CORPORATION COMMISSIO
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	922		CEMENT CIRC TO 5'
SURF	8.625	165		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/29/2013 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JEFF KLOCK Company: KCC Phone: _____

Proposed
Plugging
Method:

RUN TUBING TO BOTTOM & CIRCULATE HOLE FULL OF CEMENT. CK ANNULAS.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 08/29/2013 8:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

RAN 2 3/8 TUBING TO 925' & CIRCULATE CEMENT TO SURFACE WITH 80 SX CEMENT. POSSIBLE HOLE IN CASING AT 100 FT. WELL FLOWING FRESH WATER. PUT SWEDGE ON CASING & SQUEEZED 80 SX INTO CASING. SI PRESSURE 300 PSI. CEMENT DOWN 6' IN ANNULAS. CUT OFF & COVERED 4' BELOW GL.

KCC WICHITA
SEP 17 2013
RECEIVED

Remarks: QUALITY WELL SERVICE 60/40 4% GEL -- FEE FUND - CONTROL #20130086-001

Plugged through: TBG

District: 02

Signed _____


(TECHNICIAN)

JK