

API Well Number: 15-133-02387-0000

Spot: NE/SW/NW Sec 4 Twp 28 S Rng 19 ☒ E / ☐ W
3541 Feet from ☐ N / ☒ S Line of Section
4148 Feet from ☒ E / ☐ W Line of Section
GPS: Lat: 37.640381 Long: 95.339067 Date: 1/23/12
Lease Name: ADAMS-RICHEY Well #: ADA 29
County: Neosho Total Vertical Depth: 900 feet

Kansas Corporation Commission
District Plugging Report

Operator License No: 101 String Size Depth Pulled Comments
Op Name: KANSAS CORPORATION COMMISSION SURF - Casing 6.000
Address 1: 130 S MARKET T1 - Tubing 1 2.000 900
Address 2:
City: WICHITA
State: KS Zip Code: 67202 -

Well Type: WSW - Water Supply Well UIC Docket No.: Date/Time to Plug: 7/2/13
Plug Co License No.: 3097 Plug Co. Name: K-W OIL WELL SERVICE
Proposal Rcvd from: ROBERT KEPLEY Company Name: KW Phone: 620-431-2285

Proposed Plugging Report:

CLEAN OUT WELLS TO BOTTOM. PUMP FULL OF PORTLAND CEMENT, INSIDE AND OUTSIDE OF CASING. IF CEMENT IS PRESENT IN THE ANNULUS, CASING SHOULD BE PERFORATED IN AT LEAST 2 INTERVALS, UNLESS WELL IS DOCUMENTED AS ALT. 2 COMPLETION.

Plugging Proposal Received By: TONY ANDERSON Witness Type: PART - Partial
Date/Time Plugging Completed: 7/2/13 / KCC Agent: TONY ANDERSON

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
CLEARED BRUSH AND REMOVED JACK. PULLED 2" TUBING CUT WITH TORCH. RAN IN 1" TO 900' AND PUMPED 140 SACKS OF CEMENT STOPPED DUE TO NO CIRCULATION. THE NEXT DAY RAN IN TO 300' AND PUMPED 70 SACKS. THE LOCATION WAS THEN RESTORED.				

Remarks: CONTROL#20130001-029;CONTRACT#EVT1547;PO#14300-0000001602;GPS IN NAD 83 BY: TONY. FRANK& TOM; THE RIVER CUTS PROPERTY TO ODD SHAPES BUT SECTION IS SQUARE.

Plugged Thru: TBC RECEIVED KANSAS CORPORATION COMMISSION Plugged Due to Compliance Issue: ☐ Yes ☐ No
District: 03 'AUG 15 2013 (Technician)
CONSERVATION DIVISION WICHITA, KS Form: District Plugging Report -