

To: 1 041142
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 007-22,318-00-00
App. SW SW, SEC. 3, T 34 S, R 13 W X
515 feet from S section line
4765 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5506
Operator: Woolsey Petroleum Corporation
Name & Address: 107 N. Market
Wichita, KS 67202

Lease Name Allen J Well # 1
County Barber 165.10
Well Total Depth 5080 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 429

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address Medicine Lodge, KS

Company to plug at: Hour: 11:15 a.m. Day: 24 Month: 1 Year: 19 96

Plugging proposal received from Rick Masters
(company name) Clarke Corporation (phone) 316-886-5665

Perfs: 4 1/2" at 5043' w/150 sx cement, PBSD 5007', Perfs at 4879-4903, 4813-28, 4838-44, CIBP @ 4755', 4062-68'

1st plug sand back to 4020' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 24 Month: 1 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pushed 4 1/2" wiper plug to 4020'. Sanded back on top of wiper plug to 3900' and put 4 sx cement on top of sand bridge through dump bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 150 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3200' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form)

INVOICED
1 (813) (XXXXXX) observe this plugging.

DATE 1-30-96
WV. NO. 44760

Signed *Stephen J. Rieder* (TECHNICIAN)

RECEIVED
KANSAS CORP COMM
1996 JAN 26 P 12:00