

1 030161

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-21,331-00-01

NW NW NW, SEC. 10, T 34 S, R 11 (W) (K) (X)

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5187

Lease Name Michel 'A' Well # 1  
(AKA Big Mamu)

Operator: Silver Creek Management Corp.

County Barber

Name & Address 1900 N. Amidon Suite 221

Well Total Depth 4704 152.88 feet

Wichita, KS 67203

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address Box 206, Geneseo, Kansas 67444

Company to plug at: Hour: 9:00 AM Day: 16 Month: 4 Year: 19 84

Plugging proposal received from Allen Nicholas

(company name) Nicholas Casing Pulling (phone) 316-824-6483

were: 4 1/2 set at 4635' Perfs 4510-4517 4400

1st plug sand back to 4460 and dump 4 sx cement on top of sand

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 1 sack hulls, 10 sx gel and release 8 5/8" rubber plug and pump an additional 100 sx cement.

Bud Metz saw the last part of this plugging

Plugging Proposal Received by Steve Duvant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 11:30 Day: 16 Month: 4 Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4635' Perfs 4510-4517 4400

1st plug sand back to 4460' and dump 4 sx cement on top of sand, 2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 1 sack hulls, 10 sx gel and release 8 5/8" rubber plug and pump an additional 100 sx cement.

Bud Metz saw the last part of this plugging.

Remarks: They recovered 4025' of 4 1/2" casing. Use 60/40 Pozmix 2% gel 3% cc by  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-25-84

INV. NO. 1263  
4-16

RECEIVED  
STATE CORPORATION COMMISSION

APR 24 1984

Signed Steve Duvant  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas