

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-10006-00-01  
Spot: CNE Sec/Twnshp/Rge: 4-34S-11W  
1320 feet from N Section Line, 1320 feet from E Section Line  
Lease/Unit Name: FORESTER Well Number: 1  
County: BARBER Total Vertical Depth: 4623 feet

Operator License No.: 5506 Conductor Pipe: Size \_\_\_\_\_ feet: 150.25  
Op Name: WOOLSEY PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 247 WITH 225 SX CMT  
Address: 125 N. MARKET, SUITE 1000 Production: Size 4.5 feet: 4620 WITH 125 SX CMT  
WICHITA, KS 67202 Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/13/2003 1:15 PM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: PAUL SHELITE Company: WOOLSEY PETROLEUM Phone: (316) 267-4379

Proposed Plugging Method: CIBP @ 4450' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 01/13/2003 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PBTD 4590'. NOTCH @ 4526'. PERFS AT 4504-11'. SQUEEZED CASING LEAKS AT 2738-39' & 3360'. SET CIBP @ 4450' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID 4 1/2" CASING DOWN & RUN 2 3/8" TUBING TO SPOT PLUGS THROUGH. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

RECEIVED  
JAN 16 2003  
KCC WICHITA 1-16-03

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1950' OF 4 1/2" CASING.

Plugged through: TBG

District: 01



Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

INVOICED

DATE 1-17-03

INV. NO. 2003061087

Form CP 888  
*[Signature]*