

To: 1 051477  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-2  
API NUMBER 15-007-22,381-00-00 23 R  
S/2 SW SW, SEC. 24, T 34 S, R 11 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Operator: Pickrell Drilling Company, Inc.  
Name & Address 110 N. Market, Suite 205  
Wichita, KS 67202

330 feet from S section line  
4620 feet from E section line

Lease Name Maguire "A" Well # 1  
County Barber 132.92

Well Total Depth 4090 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123

Address 110 N. Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 5 p.m. Day: 2 Month: 10 Year: 19 91

Plugging proposal received from Doyle Folkerts

(company name) Pickrell Drilling Company, Inc. (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3000' with 50 sx cement, 2nd plug at 600' with 50 sx cement,

3rd plug at 260' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7 p.m. Day: 2 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 3000' with 50 sx cement;

2nd plug at 600' with 50 sx cement,

3rd plug at 260' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 09 1991  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(XXX) did not observe this plugging.

DATE 11-4-91

INV. NO. 33567

Signed Richard M. Lacey  
(TECHNICIAN)

R.M.L.