

To: 1 040289
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-20,981-00-00 127
SE SW, SEC. 19, T 34 S, R 11 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447
Operator: OXY USA, Inc.
Name & Address P.O. Box 26100
Oklahoma City, KS 73126-0100

Lease Name Fitzgerald "B" Well # 1
County Barber 155.35
Well Total Depth 4780 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1021

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hayes Well Service License Number 5429
Address P.O. Box 108, Attica, KS 67009

Company to plug at: Hour: 1:15 p.m. Day: 21 Month: 6 Year: 1989

Plugging proposal received from Don Herman

(company name) OXY USA, Inc. (phone) 316-532-2002

were: 5 1/2" at 4778' PBDT 4717' Perfs at 4676-96'

1st plug set CIBP at 4600' and put 5 sx cement on top of CIBP with bailer,
2nd plug pump down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, 100 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 21 Month: 6 Year: 1989

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4600' and put 5 sx cement on top of CIBP
with bailer.

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, and 100 sx cement.

Maximum pressure 900 psi and shut in 750 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3630' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (if applicable) observe this plugging.

DATE 7-5-89
INV. NO. 25164

Signed Stephen J. Pfeifer
(TECHNICIAN)