

To: 1 060712
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21094-00-00

CNESE, SEC. 26, T. 34 S, R. 11 W1/2
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License 6378

Lease Name Mayberry Well # 1-26

Operator: Hawkins Oil & Gas Inc
Name &

County Barber 154.54

Address Box 1282 Liberal,
Kansas 67901

Well Total Depth 4755 feet.

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 422

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargants Casing Pulling Ser. License Number 6547

Address 620 S. Lincoln, Liberal, Kansas, 67901

Company to plug at: Hour: 9:00 AM Day: 29 Month: October Year: 19 85

Plugging proposal received from Don Horton

(company name) Sargants Casing Pulling Ser. (phone) 316-624-7455

1st. were: Pumps 1 sbx bulls & 20 sbx cent to bottom - 2nd plug shot off 4 1/2" & pull to 450' & pump 50 sbx cent. 3rd plug lay down rest of 4 1/2" casing & build bridge @ 40' & pump 10 sbx cent filling hole to 0'. They had hole full of heavy sand before pumping each plug. They had 4 1/2" set @ 4745' w/PBTD @ 4704'. They recovered 3730' of 4 1/2" Plugging Proposal Received by Paul A. Luttis (TECHNICIAN)

Perfs were from 4652' to 82'

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:00 AM Day: 31 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sbx bulls & 20 sbx cent to bottom. 2nd plug shot off 4 1/2" pipe & pulled to 450' & pumped 50 sbx cent. 3rd plug pulled rest of the 4 1/2" & built solid bridge @ 40' & pumped 10 sbx cent filling hole to 0'. Sargants Casing pulling services pumped cement (lacked) cement. They filled the hole each time before pumping plugs with heavy mud.

Remarks: _____
(if additional description is necessary, use BACK of this form.)

INVOICED

observe this RECEIVED. STATE CORPORATION COMMISSION

Signed Paul A. Luttis (TECHNICIAN)

DATE NOV 22 1985

NOV 8 1985

INV. NO. 11124

CONSERVATION DIVISION

FORM CP-2/3 Rev. 01-84