

1 040436

7-6

15-007-21345-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 8/19/81

N/2 N/2, SEC. 31, T 34 S, R 11 W/4E

4620 feet from S section line

2640 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6006

Lease Name Yates Well # B-1

Operator: Molz Oil Company

County Barber 155.51

Name:

Address RR 2, Box 54

Well Total Depth 4785 feet

Kiowa, KS 67070

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 347

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:30 a.m. Day: 6 Month: 7 Year: 19 90

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4784' PBSD 4757' Perfs at 4740-63'

1st plug sand back to 4690' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 10 3/4" wiper plug and pump 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 11 1990  
CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 a.m. Day: 6 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4690' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 150 sx cement. Maximum pressure 350 psi and shut in 200 psi.

Note: No wiper plug. Pumped through 8 5/8" collar welded into 10 3/4" surface pipe.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3850' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 7-17-90

INV. NO. 28602