

To: 1 010012

API NUMBER 15- 007-21,618-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION S/2 N/2 NE, SEC. 35, T 34 S, R 11 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4785 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5429
Operator: Attica Gas Venture Corp., Inc.
Name & Address: 123 N. Main
Attica, KS 67009

Lease Name Lewis Well # 1
County Barber 152.75
Well Total Depth 4700 feet
Conductor Pipe: Size 13 3/8" feet 101
Surface Casing: Size 8 5/8" feet 236 ✓

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hayes Well Service License Number 5429
Address Box 108, Attica, KS 67009

Company to plug at: Hour: 3:45 pm Day: 1 Month: August Year: 19 85

Plugging proposal received from Carl Durr
(company name) Attica (phone) 316-254-7222

were: 4 1/2" at 4699' PBT 4020' Perfs at 4644-4649'; 3908-3914'
1st plug pump 50 sx cement to 3860' (common cement 2% gel 3% cc)
2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement. (60/40 Pozmix 6% gel)

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:40 pm Day: 1 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement to 3850' - 60' above perfs.
2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 250 psi

Remarks: Recovered 2970' 4 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Signed *Paul A. Luthi*
(TECHNICIAN)

DATE 8-13-85

AUG 13 1985

INV. NO. 9527
8-1