

1 060774

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,115-00-00

E/2 SW NE, SEC. 34, T 31 S, R 12 W/E  
3300 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Lease Name Cargill Well # 1

Operator: Mull Drilling Company, Inc.

County Barber 154.05

Name & Address P. O. Box 2758

Well Total Depth 4740 Simpson feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor D. R. Lauck Oil Co., Inc. License Number 5427

Address 221 South Broadway, Suite 400, Wichita, KS 67202

Company to plug at: Hour: 8:30 pm Day: 19 Month: January Year: 19 86

Plugging proposal received from Doyle Folkert

(company name) D. R. Lauck (phone) 316-263-8267

Elevation 1530

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite N/A

1st plug in the Arbuckle with 40 sx cement if 50' or more

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement

solid bridge

4th plug huls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:00 am Day: 20 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement, 2nd plug at 290' with 40 sx

cement, 3rd & 4th plugs - solid bridge - huls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JAN 27 1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form.)

INVOICED (If not observed this plugging.)

DATE FEB 5 1986

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 12356