

1070081

TO: STATE CORPORATION COMMISSION

9-10

API NUMBER 15-007-22,202-00-00  
E/2 SW NW SEC. 33, T 31 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 3300 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4290 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME ADAMS WELL # 3

TECHNICIAN'S PLUGGING REPORT COUNTY BARBER 121.88

OPERATOR LICENSE # 5393 WELL TOTAL DEPTH 3750 FEET

OPERATOR: A.L. ABERCROMBIE, INC PRODUCTION CSG: SIZE 4 1/2" FEET 3749

NAME AND RT #1 BOX 56 SURFACE CASING: SIZE 8 5/8" FEET 429'

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS 312 S MAIN, CHASE, KS 67524

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 10 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE, INC (PHONE) 316-938-2943

WERE: PERFS AT 3671-3675

1ST PLUG SAND BACK TO 3620' WITH 4 SX CEMENT ON TOP WITH BAILER, 2ND PLUG SPOT 10 SX GEL & 50 SX CEMENT AT 609', 3RD PLUG AT 445' WITH 40 SX CEMENT, 5TH PLUG AT 0-40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 9:15 AM DAY: 10 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT 9-15-98

1ST PLUG SANDED BACK TO 3620' WITH 4 SX CEMENT ON TOP WITH BAILER, 2ND PLUG SPOT 10 SX GEL & 50 SX CEMENT AT 609', 3RD PLUG AT 445' WITH 40 SX CEMENT, 4TH PLUG AT 0-40' WITH 10 SX CEMENT. GOOD CIRCULATION.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. 2000' OF 4 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (I) OBSERVE THIS PLUGGING.

DATE SEP 17 1998

INV. NO. 51309

SIGNED (TECHNICIAN) FORM CP-2/3

RECEIVED  
KANSAS CORPORATION  
SEP 17 1998  
12:40