

To: 1 040730 12-28
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-007-20804-00-01
API NUMBER 15- Completion date 10/5/79

SE SE NE, SEC. 32, T 31 S, R 12 W/E
2970 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Clarke H Well # 1

Operator: Marathon Oil Company

County Barber 141.70

Name

Address RR 1, Box 125 B

Well Total Depth 4360 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 313

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:30 a.m. Day: 28 Month: 12 Year: 19 92

Plugging proposal received from Vernon Schrant

(company name) Marathon Oil Company (phone) 316-886-5665

were: 4 1/2" at 4350' w/200 sx cement, PBSD 4165', Perfs at 4180-4220, Retainer at 4165',
Perfs at 3615-19'

1st plug pump 1 or 2 sx hulls and 30 sx cement. Stop 50' above perfs,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:15 a.m. Day: 28 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 200 lbs. hulls and 30 sx common
cement. Stopped plug at 2800',

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 950 psi and shut in 750 psi.

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2350' of 4 1/2" casing.

Additional description is necessary, use BACK of this form. Kansas
observe this plugging.

INVOICED

DATE 1-8-93

Signed Stephen J. Deuser
(TECHNICIAN)

INV. NO. 37146