

100193

STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-007-22,558-00-00

NW NW SW, SEC. 3, T 34 S, R 13 W X

2310 feet from S section line

330 feet from W X section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5506

Lease Name Allen A Well / 1

Operator: Woolsey Petroleum Corporation

County Barber 174.53

Name & Address 125 N. Market, Ste. 1000

Well Total Depth 5370 feet

Wichita, KS 67202-1775

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 219

Abandoned Oil Well Gas Well Input Well SMD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 5 p.m. Day: 5 Month: 2 Year: 19 98

Plugging proposal received from Ken MCGuire

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

was: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 600' with 50 sx cement, 2nd plug at 240' with 40 sx cement,

3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement.

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 p.m. Day: 5 Month: 2 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,

2nd plug at 240' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 18 1998

INV. NO. 50104

Signed Gary Winters (TECHNICIAN)