

11-19

To: 1 120343
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,273-00-00

C W/2 NE, SEC. 4, T 34 S, R 13 WXB
3960 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Falen "A" Well # 2

Operator: TXO Production Corporation
Name:
Address 1660 Lincoln Street, Suite 1800
Denver, CO 80246

County Barber 165.75

Well Total Depth 5100 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 391

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Trans Pac Drilling, Inc. License Number 5841

Address One Main Place, Suite 410, Wichita, KS 67202

Company to plug at: Hour: 10:30 a.m. Day: 19 Month: 11 Year: 19 89

Plugging proposal received from Gary Pugh

(company name) Trans Pac Drilling, Inc. (phone) 316-265-0226

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 450'
1st plug at 600' with 50 sx cement, 2nd plug at 430' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:30 a.m. Day: 19 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,
2nd plug at 430' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1989
CONSERVATION DIVISION
Wichita, Kansas

1127.89

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED

(if additional description is necessary, use BACK of this form.) Observe this plugging.

DATE 12-6-89

Signed Duane Rankin
(TECHNICIAN)

WELL NO. 26653