

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22432-00-00
Spot: N2S2SW Sec/Twnshp/Rge: 2-34S-13W
990 feet from S Section Line, 1320 feet from W Section Line
Lease/Unit Name: MOTT D Well Number: 1
County: BARBER Total Vertical Depth: 3688 feet

Operator License No.: 30972
Op Name: PETROGLYPH OPERATING COMPANY
Address: PO BOX 1839
HUTCHINSON, KS 67504

Conductor Pipe: Size feet: 3119.86
Surface Casing: Size 8.625 feet: 371 WITH 200 SX CMT
Production: Size 4.5 feet: 3688 WITH 110 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/21/2002 1:15 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SAND BACK TO 3625' & DUMP 4 SX CMT ON TOP WITH BAILER. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/21/2002 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 3684'. PERFS AT 3673-3675'. SANDED WELL BACK TO 3540' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PUMPED 8 5/8" SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG & 100 SX CMT. MAXIMUM PRESURE 500#. SHUT IN PRESSURE 250#.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2900' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

RECEIVED

MAR 25 2002

DATE March 28-02

MAR 28 2002

INV. NO. 2002061578

KCC WICHITA

MP

FORM 2/3