

1 060955

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,733-00-00
250' N 60' W OF
NW SW NE, SEC. 33, T 30 S, R 15 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Operator: Texas Energies, Inc.
Name & Address: P.O. Box 947
Pratt, KS 67124

3880 feet from S section line
2370 feet from E section line

Lease Name Cross Well # 1-33
County Barber 152.82

Well Total Depth 4702 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 336

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 4 Month: 5 Year: 1987

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4621' PBD 4579' Perfs at 4284-88', 4300-4303'

1st plug pump 1 sx hulls, 20 sx cement, to bottom - stop plug at 2680',

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 4 Month: 5 Year: 1987

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement - stopped plug at 2684',

Maximum pressure 1500 psi and shut in 1300 psi. Jack Luthi saw bottom plug.

2nd plug pumped 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 125 sx cement. Maximum pressure 900 psi and shut in 500 psi.

Paul Luthi saw all of 2nd plug.

Remarks: Recovered 2615' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.) MAY 6 1987

INVOICED (if desired) observe this plugging.

DATE 5-7-87

INV. NO. 16820

Signed Paul A. Luthi
(TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION