

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22412-00-00
Spot: S2SWNW Sec/Twnshp/Rge: 11-30S-13W
2970 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: LAWRENZ Well Number: 1-11
County: BARBER Total Vertical Depth: 4800 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 6427 EAST KELLOGG
WICHITA, KS 67207

Conductor Pipe: Size 13.375 feet: 235 \$156.00
Surface Casing: Size 8.625 feet: 1036 WITH 350 SX CMT
Production: Size 4.5 feet: 4780 WITH 225 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/16/2001 9:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: TERRY BAIRD Company: FG HOLL Phone:

Proposed Plugging Method: SAND TO 4260' & 4 SX CMT. 1ST PLUG AT 1060' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. IF 13 3/8" X 8 5/8" NO CEMENTED TO SURFACE PUMP 100 SX CMT DOWN ANNULUS

Plugging Proposal Received By: STEVE PFEIFER
Date/Time Plugging Completed: 11/16/2001 10:15 AM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4767'. PERFS AT 4318-4330 & 4529-35'. SANDED BACK TO 4255' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1060' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICE. RECOVERED 3027' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED

DEC 07 2001
KCC WICHITA

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 12-10-01

INV. NO. 2002061049

NOV 19 2001

AP

Form CP-233
[Signature]