

To: 1 040728 12-28
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,569-00-00

C S/2 SE, SEC. 11, T. 30 S, R. 13 W/E
660 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Means Well # B-2

Operator: Marathon Oil Company
Name & Address RR 1, Box 125 B
Medicine Lodge, KS 67104

County Barber 97.50

Well Total Depth 3000 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 375

Abandoned Oil Well _____ Gas Well Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 2 p.m. Day: 28 Month: 12 Year: 1992

Plugging proposal received from Vernon Schrant

(company name) Marathon Oil Company (phone) 316-886-5606

were: 4 1/2" at 2940' w/150 sx cement, PBTD 2915', Perfs at 2802-2808'

1st plug sand back to 2750' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 28 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 2750' and dumped 4 sx cement on top of sand
bridge through bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 1000 psi and shut in 450 psi.

JAN 4 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1850' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

1 (old / ~~XXXXXX~~) observe this plugging.

DATE 1-8-92

Signed Steve Pfeifer
(TECHNICIAN)

INV. NO. 37144