

1 010234

APR 22 1987

-00.01

162

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,625-A

SE SE NW, SEC. 13, T 30 S, R 13 (W/E)

2970 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Means Well # 1

Operator: Raymond Oil Company, Inc.

County Barber 153.23

Name & Address P.O. Box 48788

Well Total Depth 4730 feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 251

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:45 a.m. Day: 22 Month: 4 Year: 19 87

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4678' PBD 4618' Perfs at 4472-80, 4442-6, 4254-8'

1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 a. Day: 22 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 5 sx cement on top of sand through bailer, used common cement,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Maximum pressure 700 psi and shut in 300 psi.

Remarks: Recovered 3400' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied. (If additional description is necessary, use BACK of this form.)

INVOICED

STATE CORPORATION COMMISSION

DATE 4-29-87

APR 28 1987

Signed [Signature] (TECHNICIAN)

INV. NO. 16673

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 01-84