

1041359

TO: STATE CORPORATION COMMISSION

7-14

API NUMBER 15-007-22,388-00-00
C W/2 NE SE SEC. 9, T 30 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 1985 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LAWRENZ WELL # 1 TWIN

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER

OPERATOR LICENSE # 5506

WELL TOTAL DEPTH 4730 153.73 FEET

OPERATOR: WOOLSEY PETROLEUM CORPORATION PRODUCTION CSG: SIZE 5 1/2" @ 4692' WITH 125 SX

NAME AND PO BOX 168 SURFACE CASING: SIZE 8 5/8" @ 1024' WITH 425 SX

ADDRESS MEDICINE LODGE, KS 67104 CONDUCTOR CSG: SIZE 1 3/8" @ 108' WITH 110 SX

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 3:30 PM DAY: 14 MONTH: 07 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 4534-60, 4418-38

SANDED BACK TO 4340' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER.

PUMPED DOWN 8 5/8" WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8" WIPER

PLUG, & 100 SX CEMENT. MAXIMUM PSI = 500#. SHUT IN WITH 100#.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 14 MONTH: 07 YEAR: 1999

ACTUAL PLUGGING REPORT

SANDED BACK TO 4340' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER.

PUMPED DOWN 8 5/8" WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8" WIPER

PLUG & 100 SX CEMENT. MAXIMUM PSI = 500#. SHUT IN WITH 100#.

RECEIVED

STATE CORPORATION COMMISSION

7-22-99 JUL 22 1999

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3400' OF 5 1/2" CASING TO KANSAS
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DAD) DESERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer (TECHNICIAN) FORM CP-2/3

DATE 7-26-99

INV. NO. 60074

Handwritten initials and a circled 'R'.