

1 121055 7-27

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 75' W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,179-00-00

of SW NW SEC. 9, T 30 S, R 13 W/E
3300 feet from S section line

4695 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4419

Lease Name Lemon B Well # 1

Operator: Bear Petroleum, Inc.
Name & Address: P.O. Box 438
Haysville, KS 67060

County Barber 154.38

Well Total Depth 4750 feet

Conductor Pipe: Size 13 3/8 feet 112

Surface Casing: Size 8 5/8 feet 1061

Abandoned Oil Well Gas Well Input Well SNO Well D&A

Other well as hereinafter indicated

Plugging Contractor Bear Petroleum, Inc. License Number 4419

Address P.O. Box 438, Haysville, KS 67060

Company to plug at: Hour: 1 p.m. Day: 27 Month: 7 Year: 19 95

Plugging proposal received from Dick Schremmer

(company name) Bear Petroleum, Inc. (phone) 316-524-1225

were: 5 1/2" at 4730' w/150 sx cement, PBTD 4720', Perfs at 4564-68, 4616-20, CIBP at 4190',
Perfs at 4144-50'

1st plug sand back to 4090' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10, sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 p.m. Day: 27 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4090' and dumped 5 sx cement on
top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 5 sx gel, 50 sx cement,

15 sx gel, 100 lbs. hulls, released wiper plug and pumped 100 sx cement.

Pumping pressure 0-900 psi and shut in 700 psi.

RECEIVED STATE CORPORATION COMMISSION

JUL 31 1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3208' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE AUG 02 1995

Signed [Signature] (TECHNICIAN)

INV. NO. 43226 7-27